

# **Technical Specification:**

The information contained in this specification is offered by the Princess Theatre for visiting companies, artists and hirers. Please note the specifications contained in this document are correct at the time of issue and are subject to change and availability. Additional crew, other than duty technician and equipment maybe subject to a recharge.

Contact: tech@theprincesstheatre.co.uk / 01278554990

#### **Access**

There is a small free private car park at the rear of the theatre for two company vehicles. More can be made available at request. Loading can be completed at the double height dock door and vehicles moved into the car park as soon as possible after load in completion. We are found at **TA8 1EH**. We do not have any in house load in ramp. The stage is 5 steps upwards from the road level.

Please be aware of The Princess Theatre Health and Safety Policy for Visiting Companies forms part of the contract with the visiting company.

#### Information

Audience: Capacity of 200 seated and 350 standing with a retractable raked seating bank.

Catering maybe provided if requested in advance with Hellend's Kitchen. A menu is located at the end of this document.

# **Dressing rooms & Back Stage**

There are 2 dressing rooms backstage, One large (Which can be divided into 2) one smaller both with access to stage right. There is a backstage corridor to stage left which requires going down and upstairs each side. There is a large area just off stage left which can be used as a waiting area. Both dressing rooms have audio and video show relay.

We regret that there is no disabled access to stage.

# **Stage & Wing Dimensions**

No Rake, Not Sprung, Permanent harlequin black dancefloor The stage is fully Black boxed

Depth	Front of Stage to Back Wall	5.84m
Width	Prosc Opening	7.47m
	SR Wall to SLWall	10.60m
Height	Prosc	5m
	Stage width	8 08m

#### **Loading door:**

Height to stage:	2.15m
Width:	1.98m



**Performance Area** Demountable Stage units with Black Harlequin Performance Surface.

### Masking & Tabs

X3 8m W x 1m H - BWS Stage Border
X4 1m W x 5m H - BWS Stage Leg
X2 4.5m W x 5m H - BWS Stage Black — Upstage masking on swipe track
X1 8m W x 5m H White Canvas Cyclorama at rear of stage on swipe
X2 4.5m W x 4.3m H - Cotton Velvet WINE NDFR Drape Red Velvet Tabs, manual winch SR
X2 4.5m W x 5m H - BWS Stage Black Mid Stage Black (Located on Manual Winch 3, pully operated SR)

#### **Flying**

Full Height If masking set to 4m
Rear CYC / Blacks on swipe track fixed on up stage wall
Fly Floor SL at Stage level
10 Hemp Sets to Fly Floor, 30kg SWL
Hemp 1 Permanently used for Projector screen
5 Manual Winches to Fly Floor, Max UDL 300kg, LX1 - LX4

### Video & Relay:

Control Room, Dressing Rooms, Stage Left, Stage Right and the Stage Right corridor have an infra-red video feed of the stage.

There is a back stage announcement mic located stage right at the DSM position.

Audio show relay is available throughout the building and in all dressing rooms.

#### **Power**

63A, 32A (Single Phase) and 16A Power is situated DSR with a 32A run to DSL – please be aware the 16A feeds are used for our house grid.

### There no three phase power

### **FOH Positions**

Lighting & follow spots can be operated in the control room at the rear of the auditorium. There are windows with good visibility of stage. These windows can be opened if required.

Sound can be operated from the middle window of the control room. This window can be removed if needed and the desk is positioned forward into the auditorium.

There is also a production / sound desk table that can be located in the auditorium. This must be agreed in advance for seating to be blocked out.

# **Projection & Playback**

Projectors	1X Optoma DLP EX531P Projector (Portable) VGA ONLY*	
	1X Hitatchi Short Throw Data Projector	
	1X Epson EB-L1490U Mid Throw Projector* (Installed in	
	control room) suitable for projecting on CYC / Screen	
Screen	Electric Projector screen mounted on hemp 1 – 3985 x	
	2490cm	
Processing	1X Denon DN-700AV (Installed in control room)	
	2014 Mac Mini (Qlab)	
Blu Ray / DVD	1X Denon Blu Ray Player (Installed in control room)	
	1X Toshiba HDMI DVD Player	
	CAT5- HDMI Adapters for stage connection to projector	

<sup>\*</sup>Rechargeable Item - Additional equipment maybe sourced by The Princess Theatre where needed subject to agreed recharge.

# **Lighting Specification**

- Universe 1 to dimmers (Hard Patched 1-48)
- Universe 2 to stage rack and buffer
- 48 Channels of 2.5kw dimming from Strand LD90's located Stage Right
- Bridge: circuits 1 16
- SR Boom circuits 1 5 (paired with bridge)
- SL Boom circuits 12 16 (paired with bridge)
- LX 1 circuits 17 26,
- LX 2 circuits 27 34
- LX 3 circuits 35 40,
- LX 4 (CYC) circuits 41 46
- Floor circuits 47-48

Fixture	Quantity
Elumen8 Alu HexPar64 LED Par	12
Lumin8 tri pixel batten	4
ETC S4 JR	12
Selecon acclaim inc. barn doors	12
Strand quartet pc inc. barn doors	3
Strand prelude 16/30	8
Strand Quartet Profile 15/25	6
Thomas PAR 64	8
Moonlight 1000 Follow Spots*	3
ETC S4 Jr M Size Gobo Holder	4
Strand Prelude B Size Gobo Holder	4

There is a small selection of LEE filters on site, but we request that the company provides their own Gel where required.



# **Lighting Control**

ETC ION 3 with 2 screens and 20 fader wing iPad Riggers Remote DMX feed on each bar, FOH and DSR

- Please email for a copy of our current house LX plan & EOS file if required

\*Please note our house lights are NOT DMX controllable and are operated by a push switch behind the lighting position.

Stage Effects: & Rigging

Martin Gem Haze Machine*	1
Outrig Arms	6
4ft Lighting Booms	2
Visage 4 Channel IEC Dimmer	2

### Cable:

There is a selection of XLR, Jack, DMX, Power (13A/15A/16A) and adapters on site.

## **Audio Specification**

Desk:	Allen and Heath QU16
Speakers	2 x FBT 15" Powered Speakers
	2X W Audio PSR15A
	2X RCF ART MK2 (Used as Stage Monitors)
	4X RCF ART MK5 (Installed FOH)
	2X Mackie 18' Active Subs
	1X QTX Battery Speaker with Handheld
	Wireless Mics
Amplifiers	1X RCF 600W amplifier (CINEMA Only)
	1X Crown 2502 (FOH)
	1X Peavy 1500 (Stage Monitors)
Multicore / CAT5	2X CAT5E lines to each side of stage from
	control room (1 is used for house sound
	system)
	1X 12way installed analogue multicore
	between control room and DSR
	Allen and heath AR2412
	15M Analogue 16/4 Multicore
Communication	Show relay (FOH / Back stage) from control
	room.
	X6 Stonewood Audio Beltbacks & Headset
	1X Canford base Station
	Hearing loop installed in auditorium
	X2 Show Relay 100v Amp (ROH & FOH)
	Denon Rack Mixer (FOH Music)

Mica Chanda Di Daves	2V Dobringer DI 1000
Mics, Stands, DI Boxes	2X Behringer DI 1000
	1X Behringer DI120
	2X Audio Technica ATM33a
	3X Crown PCC160
	1X Audiotechnica MB1k
	1AKG D9
	1X Audiotechnica ATM41HE
	2X Sure SM58
	2X Sure SM57
	1X Sure Beta 52A
	3X NJD NJ661AB Drum Mic
	2X Audio Technica AMT33a Condenser
	8X Tall Mic Stands
	1X Tall Mic Stand Round Base
Keyboard	Yamaha / Piano Stool

#### **House Rules**

- No Smoking inside the building Please use dedicated smoking areas
- Visiting company members MUST sign in
- Any incoming electrical appliance **MUST** have a valid PAT Test
- No glass to be taken on stage
- All visiting company members to be aware of the evacuation procedure
- Any accidents must be reported to the duty technician or duty manager
- All fire exits must be kept clear and fire doors not propped open
- Access to ladders & working at height MUST be approved and supervised by a member of house staff
- All flying operations will require a minimum of two persons present
- The Theatre reserves the right to monitor and if necessary, limit the sound levels for any given performance
- No Smoke / Haze to be used until the duty tech has been informed

### **Working Regulations**

- No Alcohol to be consumed before or during the event
- The Working Time Regulations 1998 an 11-hour break between working shifts must be scheduled for all staff members. Suitable breaks must be scheduled to ensure the health and wellbeing of all staff.
- All working crew must wear suitable PPE where necessary and steel toe cap safety footwear

All crew must be competent, well rested and sober, the visiting company must provide a suitably competent person to supervise the unloading and loading of trucks. The Princess Theatre reserves the right to delay any activity that it deems unsafe until sufficient crew can be deployed.

